

Novel Concepts for the Compression of Large Volumes of CO₂

Southwest Research Institute Team:

J. Jeffrey Moore, Ph.D.

Hector Delgado

Andrew Lerche

Timothy Allison, Ph.D.

Brian Moreland

Project Funded by DOE NETL

DOE PM: Mr. Timothy Fout

Co-Funded by Dresser-Rand and BP





Project Motivation



- CO₂ capture has a significant compression penalty - as high as 8 to 12%.
- Final pressure around 1,500 to 2,200 psia for pipeline transport or re-injection.
- Based on a 400 MW coal plant, the typical flow rate is ~600,000 to 700,000 lbm/hr.
- Project goal: Double-digit reduction of compression power for CO₂ capture
- Many thermodynamic processes studied.
- Several challenges with the application discussed.




Project Overview




- Phase I (Completed)
 - Perform thermodynamic study to identify optimal compression schemes
- Phase II (Complete in 2010)
 - Pilot testing of two concepts:
 - Isothermal compression (test underway)
 - Liquid CO₂ pumping (complete)

- Only CO₂ stream considered




Compression Technology Options for IGCC Waste Carbon Dioxide Streams



Optimal solution combines inter-stage cooling and a liquefaction approach.



Summary of Thermodynamic Analysis for IGCC Plant



Option	Compression Technology	Power Requirements	% Diff from Option A	Cooling Technology
A	Conventional Dresser-Rand Centrifugal 10-stage Compression	23,251 BHP	0.00%	Air-cool streams between separate stages
B	Conventional Dresser-Rand Centrifugal 10-stage Compression with additional cooling	21,522 BHP	-7.44%	Air-cool streams between separate stages using ASU cool N2 stream
C.1	Isothermal compression at 70 degF and 80% efficiency	14,840 BHP	-36.17%	Tc = 70 degF inlet temp throughout
C.4	Semi-isothermal compression at 70 degF, Pressure Ratio ~ 1.55	17,025 BHP (Required Cooling Power TBD)	-26.78%	Tc = 70degF in between each stage.
C.7	Semi-isothermal compression at 100 degF, Pressure Ratio ~ 1.55	17,979 BHP (Required Cooling Power TBD)	-22.67%	Tc = 100degF in between each stage.



Summary of Thermodynamic Analysis for IGCC Plant Cont.




Option	Compression Technology	Power Requirements	% Diff from Option A	Cooling Technology
D.3	High ratio compression at 90% efficiency - no inter-stage cooling	34,192 BHP	47.06%	Air cool at 2215 psia only
D.4	High ratio compression at 90% efficiency - intercooling on final compression stage	24,730 BHP	6.36%	Air cool at 220 and 2215 psia
E.1	Centrifugal compression to 250 psia, Liquid cryo-pump from 250-2215 psia	16,198 BHP (Includes 7,814 BHP for Refrigeration) ¹	-30.33%	Air cool up to 250 psia, Refrigeration to reduce CO ₂ to -25degF to liquify
E.2	Centrifugal compression to 250 psia with semi-isothermal cooling at 100 degF, Liquid cryo-pump from 250-2215 psia	15,145 BHP (Includes 7,814 BHP for Refrigeration) ¹	-34.86%	Air cool up to 250 psia between centrifugal stages, Refrigeration to reduce CO ₂ to -25degF to liquify

Note: Heat recovery not accounted for.




- Liquefaction process
 - Utilize a refrigeration system to condense CO₂ at 250 psig and -12°F.
 - Liquid then pumped from 250 to 2,200 psig.
 - Requires significantly less power to pump liquid than to compress a gas.
 - The cost of the refrigeration system must be accounted for.

Liquefaction/Pumping Compression




Integrally Geared Isothermal Compressor



- Integrally geared can achieve near isothermal compression
- Can contain up to 12 bearings, 10 gas seals plus gearbox
- Typically driven by electric motor
- Impellers spin at different rates
 - Maintain optimum flow coef.


Single-Shaft Multi-stage Centrifugal Compressor



- Multi-stage centrifugal proven reliable and used in many critical service applications currently (oil refining, LNG production, etc.)
- Fewer bearings and seals
 - (4 brgs & seals for 2 body train)
- Can be direct driven by steam turbine



Project Goals



- Develop internally cooled compressor stage that:
 - Provides performance of an integrally geared compressor
 - Has the reliability of a in-line centrifugal compressor
 - Reduces the overall footprint of the package
 - Has less pressure drop than a external intercooler
- Perform qualification testing of a refrigerated liquid CO₂ pump




Phase 2 Project Plan




- Experimentally validate thermodynamic predictions.
- Two test programs envisaged:
 - Liquid CO₂ pumping loop
 - Closed-loop CO₂ compressor test with internal cooling
- Power savings will be quantified in both tests.

- Investigate an internally-cooled compressor concept
 - Red - CO₂ flow path through compressor stage
 - Blue - Liquid cooling in the diaphragm
 - Grey - Solid




- Predicted temperature in return channel with and without internal cooling.



Without Heat Transfer




With Heat Transfer




Case 4- Conjugate heat transfer model with enhanced heat transfer coefficients to simulate ribbed surfaces for the cooling liquid





Case 4 - Conjugate heat transfer model with enhanced heat transfer coefficients to simulate ribbed surfaces for the cooling liquid



Temperature Rise and Pressure Drop of CFD Models




Test Rig Construction




- Driven by 700 hp electric motor through gearbox
- Torquemeter installed to measure power
- Loop rated to 300 psi suction and 500 psi discharge
- Test speeds up to 14,300 rpm
- Instrumentation measures:
 - Total temperature and pressure at stage inlet and discharge
 - Total temperature and pressure at internal locations within the stage
 - Flow rate, power, and speed
 - Cooling water flow rate and delta-T
- Testing to begin later this month



- Testing will measure pump efficiency
- Validate pump design
- Measure NPSH requirements looking for signs of cavitation
- Cryostar will supply the pump
 - 250 KW, 100 gpm, 53,000 lbm/hr



- Vessel layout showing elevated reservoir and knock-out drum
- Pump is mounted at ground level.
- Orifice run located between pump and control valve (in supercritical regime)



Loop Construction






Loop Completed





Data Acquisition Code



DOE Pump Test Rig Software




Main Screen HvsQ Temp Strip Pressure Strip Raw Data Values Valve Control Gas Comp Config

Quit

Performance Results Cluster

- 249.174 Psuc [psia]
- 11.8384 Tsuc [deg F]
- 2099.88 Pdis [psia]
- 17.6525 Tdis [deg F]
- 4151.49 Head [ft]
- 58.6289 Flow [gpm]
- 241.287 Pump Brake hp [hp]
- 63.3125 Pump Hydraulic hp [hp]
- 26.2395 Pump Eff [%]
- 3506.79 Speed [rpm]

- Current
- Past Values
- Control Line
- Snapshots
- 3510 rpm
- 2500 rpm
- 1578 rpm



Record Snapshot

Nrecords: 0

Nsnapshots: 2

Speed [rpm]

3507

Replay Loop Time (ms)

5000

Pause Playback

PAUSE

Replay Point

6005

Time

17:20:23.32

Import Map

VFD Speed [rpm] Throttle Valve Close % Vent Valve Close %

VFD Speed [rpm]

0

3580.0

3000.0

2500.0

2000.0

1500.0

1000.0

500.0

0.0

STOP VFD

Throttle Valve Close %

0

100.00

80.00

60.00

40.00

20.00

0.00

OPEN VALVE

Vent Valve Close %

100

100.00

80.00

60.00

40.00

20.00

0.00

Tank P [psia]

14.0214

Desired Tank P

120

Tank P Control Or

CLOSE VALVE





Pump Conditions

- Heater On?
- OK to Start?

	Current Value	Alarm Value	Trip Value
Lantern T [deg F]	70.7067	-4	N/A
Bearing T A [deg F]	157.111	230	239
Bearing T B [deg F]	149.746		
Seal Gas T [deg F]	76.0054	50	32
Seal Gas DP [bar]	2.92192	2.2	1
Seal Gas Flow Trip [A]	0.003268	N/A	0.01
Suction P [psia]	249.174	N/A	200




Test Results









Test Results









Dynamic Data – Design Point







Dynamic Data – Minimum Flow Point





Dynamic Suction Pressure Waterfall while Throttling





Phase 2 Testing Summary




- Pump Testing
 - Pump performed well matching the measured performance during factory testing on LN2
 - Met discharge pressure goals
 - LCO2 introduced no mechanical issues for the pump
 - Vibration levels were reasonable
 - A subsynchronous vibration occurred at minimum flow point but only at very low flow rates
- Compressor Testing
 - Intercooled diaphragm designed and fabrication complete
 - Internal instrumentation being installed
 - Testing later this month
 - Patent has been filed



Future Testing



- Pump Testing
 - Perform testing at lower suction pressure
 - Demonstrate performance of the pump over a wider operating range
 - Will record performance, dynamic suction pressure, and vibration throughout test
- Compressor Testing
 - Repeat tests at higher suction pressure
 - Obtain heat transfer effectiveness at high Reynolds numbers



Questions???

www.swri.org

Dr. J. Jeffrey Moore
Southwest Research Institute
(210) 522-5812
Jeff.Moore@swri.org