

Sonja Salmon, Alan House, Charles Freeman, Kayte Denslow, Joe Remias, Balraj Ambedkar, Vinay Mulgundmath, Saravanan Swaminathan







Proudly Operated by Battelle Since 1965



29th International Pittsburgh Coal Conference October 16, 2012




Notices

ACKNOWLEDGEMENT OF GOVERNMENT SUPPORT. This material is based upon work supported by the Department of Energy under Award Number DE-FE0007741.

DISCLAIMER. This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.



Agenda



- Project Overview
 - Project Partners and Objective
 - Process Concept
- Laboratory Validations
 - Ultrasonic Unit Batch Testing
 - Enzyme-Solvent Compatibility
 - Absorption Kinetics
- Next Steps
 - Prefeasibility Assessment
 - Plans for Bench-scale Evaluation



Project Overview

Project Participants









Ultrasonics & Aspen®

Full Process Analysis

Enzymes & Solvents

Kinetics & Bench-scale Tests

- DOE Project Manager: Andrew Jones
- Project Number: DE-FE0007741
- Total Project Budget: \$2,088,643
- Project Duration: Oct. 1,2011 Dec. 31, 2014

DOE Program Objectives

Develop solvent-based, post-combustion technology that

- Can achieve ≥ 90%
 CO₂ removal from coalfired power plants
- Demonstrates progress toward the DOE target of <35% increase in LCOE.




Project Objective

Complete a *bench-scale study* and corresponding full technology assessment to validate the potential in meeting the DOE Program Objectives of a *solvent-based post-combustion carbon dioxide capture* system that <u>integrates</u>

$$CO_2 + H_2O + K_2CO_3 \leftrightarrow 2KHCO_3$$








- a low-enthalpy, aqueous potassium carbonate-based solvent
- with an absorption-enhancing carbonic anhydrase enzyme catalyst
- and a flow through ultrasonicenhanced regenerator
- in a re-circulating absorptiondesorption process configuration



Process Concept



Advantages

- ➤ Low enthalpy, benign solvent (catalyzed aq. 20% K₂CO₃)
 - K₂CO₃ ΔH_{rxn} 27 kJ/mol CO₂
 - MEA ΔH_{rxn} 83 kJ/mol CO₂
- ➤ Potential for ~50% regeneration energy vs. MEA

- Challenges
- ➤ Demonstrate atmospheric regeneration at 70°C enabled by ultrasonics
- Demonstrate overall techno-economic feasibility
 - energy demand
 - enzyme requirement



Laboratory Validations – Part 1

- Ultrasonic Unit Batch Testing
 - Demonstrated CO₂ release via ultrasonic energy addition
 - 1/3rd of target defined by ASPEN®-predicted vacuum
 - Established preliminary settings for ultrasonic power, frequency, exposure times, and need for continuous bubble removal




Ultrasonics Regeneration Mechanism

- Create a population of seed bubbles above a critical radius via ultrasonic cavitation in the liquid
- Bubbles expand and shrink in an ultrasonic field
 - Expanding bubbles = lower pressure/ higher surface area
 - Shrinking bubbles = higher pressure/ lower surface area
- Rectified diffusion results when expanding bubbles allow for a biased transfer of dissolved gas into the bubble from solution
 - Frequency optimization likely required due to its impact on the threshold pressure, and bubble growth
- Remove bubbles grown via rectified diffusion before they can dissolve back into the liquid





PNNL Lab Ultrasonic Desorption System Schematic







PNNL's Batch Lab Ultrasonic Desorption System

Gas Exit w/ Condenser

Vessel

Temperature Controlled Bath

Ultrasonic Horn (inverted horn configuration)



Solvent Recirculation Lines

- Bubbles expand and shrink in an ultrasonic field
- Rectified diffusion results when expanding bubbles allow for a biased transfer of dissolved gas into the bubble from solution
- Remove bubbles before they can dissolve back into the liquid






Photographs of Ultrasonic Desorption







Loaded Solvent at 70°C – No Sonication



Loaded Solvent at 70°C – With Sonication




Significant agitation/ bubbling observed when ultrasonic power added to CO₂ loaded 20% K₂CO₃ solution at 70°C

Proudly Operated by Battelle Since 1965

tight headspace



Batch Test Results for Ultrasonic Regeneration



- Testing with 20 wt% K₂CO₃ solvent loaded to 4.6 wt% CO₂
- ASPEN (equilibrium) projections of CO_2 release at 6 psia = 0.96%
- Total CO_2 release observed = 0.67% (0.25% from ultrasonic effect)
 - Likely impacted by re-dissolution of CO₂
- Slow CO₂ release rates observed
 - Further evaluation needed





Energy Projections for Ultrasonic Regeneration

- Commercial water sterilization = 0.24 to 0.79 kJe/ kg of water
 - Based on developed applications for ship ballast treatment [1]
- ► Initial batch testing for CO₂ regeneration = 4.9 kJe/ kg of solvent
 - Laboratory horn used. Poor CO₂ removal (significant re-dissolution)
 - Demonstrated value = 10.3 kJe /mol of CO₂, 0.021 kg of CO₂ removal per kg of recirculated solvent recirculation assumed.
- Full-scale CO_2 regeneration system estimate = 1.5 kJe/ kg of solvent
 - Based on (conservative) tube sonication configuration
 - Equates to just over 11 MWe of parasitic power for the ultrasonic system in the 500 MWe reference system

[1] "Ballast water treatment technology, Current status," February 2010 (http://www.lr.org/Images/BWT0210_tcm155-175072.pdf)






Laboratory Validations – Part 2

- Ultrasonic Unit Batch Testing
 - Demonstrated CO₂ release via ultrasonic energy addition
 - 1/3rd of target defined by ASPEN®-predicted vacuum
 - Established preliminary settings for ultrasonic power, frequency, exposure times, and need for continuous bubble removal
- Enzyme-Solvent Compatibility
 - Lab results show robustness to simulated process pH, ultrasonics, and absorber temp. with (manageable) losses at increased temp.




Producing Enzymes for Industrial Applications






Enzyme-Catalyzed CO₂ Sorption Mechansim

Carbonic anhydrase catalyzes (increases kinetic rates) the hydration of CO_2 and dehydration of bicarbonate resulting in enhanced absorption and desorption of CO_2 into and out of a CO_2 absorber solvent.






Enzyme Compatibility with Ultrasonic Treatment



• Enzyme tolerates initial ultrasonic tests with no apparent loss of activity



Enzyme-solvent Compatibility



- Demonstrates high robustness in working solvent at 40°C
- Demonstrates limited (but nevertheless useful) robustness at 70°C
- Data used for initial estimation of solvent replenishment rate in prefeasibility

Solvent: aq. 22% $K_2CO_3/KHCO_3$ with 3 g/L enzyme and adjusted to lean pH




Laboratory Validations – Part 3

- Ultrasonic Unit Batch Testing
 - Demonstrated CO₂ release via ultrasonic energy addition
 - 1/3rd of target defined by ASPEN®-predicted vacuum
 - Established preliminary settings for ultrasonic power, frequency, exposure times, and need for continuous bubble removal
- Enzyme-Solvent Compatibility
 - Lab results show robustness to simulated process pH, ultrasonics, and absorber temp. with (manageable) losses at increased temp.
- Absorption Kinetics
 - Temperature had minimal impact on mass transfer over the absorber temperature range studied
 - Initial enzyme loading for process established



UK-CAER Wetted Wall Column Schematic








novozymes*

UK-CAER Mass Transfer Results






- Solvent: aq. 20% K₂CO₃ + carbonic anhydrase
- Temperature had minimal impact on mass transfer over the absorber temperature range studied



UK-CAER Mass Transfer Results





- Solvent: aq. 20% K₂CO₃ + carbonic anhydrase
- Achieved Initial Milestone Enzyme-catalyzed Solvent Kinetics (Mass Transfer)



Laboratory Validations - Summary

- Ultrasonic Unit Batch Testing
 - Demonstrated CO₂ release via ultrasonic energy addition
 - 1/3rd of target defined by ASPEN®-predicted vacuum
 - Established preliminary settings for ultrasonic power, frequency, exposure times, and need for continuous bubble removal
- Enzyme-Solvent Compatibility
 - Lab results show robustness to simulated process pH, ultrasonics, and absorber temp. with (manageable) losses at increased temp
- Absorption Kinetics
 - Temperature had minimal impact on mass transfer over the absorber temperature range studied
 - Initial enzyme loading for process established
 - ➤ Lab results were provided for prefeasibility study

novozymes* Rethink Tomorrow

Preliminary Technical and Economic Feasibility

Overall CO₂ Capture Reaction

$$CO_2 + H_2O + K_2CO_3$$
 CA Enzyme 2KHCO₃

- Aspen Plus® (with Radfrac) used for Process modeling for absorption
- AspenTech's Capital Cost Estimator® along with budget supplier quotations used for Cost Estimation of the PCC Components
- Preliminary techno-economic feasibility and sensitivity studies performed based on the fixed coal feed rate as per Case 10 (MEA-based) for the enzyme enhanced K₂CO₃ solvent.
- Four methodologies of regeneration have been investigated:

Case 1: Vacuum Stripping using LP steam

Case 2: Vacuum Stripping using VLP steam

Case 3: Ultrasonic regeneration using electrical energy

Case 4: Ultrasonic regeneration using VLP steam





Conclusions and Recommendations

- Preliminary techno-economic evaluation has been completed for the process integrated with a subcritical coal-fired power plant indicating net efficiency improvement of 25% versus Case 10.
- Net Plant Efficiency (on HHV basis) and LCOE (\$/MWh_e):

| | | Net efficiency | LCOE (\$/MWh _e) |
|--|-------------------------|-----------------|-----------------------------|
| | Case 10 | 24.9% | 119.6 |
| Power Equivalent of 0.0911 Kwh/lb of steam | Vacuum Regeneration | 24.34% - 29.97% | 112.92 - 125.23 |
| | Ultrasonic Regeneration | 26.63% - 31.41% | 108.90 - 117.50 |
| Power Equivalent of 0.0665 Kwh/lb of steam | Vacuum Regeneration | 24.07% - 27.75% | 117.56 - 126.06 |
| | Ultrasonic Regeneration | 24.41% - 29.19% | 113.02 - 123.29 |

- Challenges that will be investigated in the next phases of the project are:
 - Validation and optimization of the performance, design of the ultrasonic regeneration
 - Reduction in dosing quantity of the enzyme
 - Further investigation of the option to utilize a VLP for solvent regeneration
 - Utilization of alternative materials of construction to reduce the capital cost of plant





Project Schedule – Next Steps

- Task 1 Project Management and Planning
- Task 2 Process optimization
 - Ultrasonic Unit Optimization
 - Solvent & Enzyme-Solvent Compatibility Optimization
 - Solvent Physical Properties & Kinetic Measurements
 - Design Integrated Bench-Scale System
- Task 3 Initial Technical & Economic Feasibility
- Task 4 Bench Unit Procurement & Fabrication
- Task 5 Unit Operations Shakedown Testing & Integration
- Task 6 Bench-scale Testing
- Task 7 Full Technology Assessment



12/2014



Acknowledgements

DOE-NETL

Andrew Jones

PNNL

Charles Freeman (PM) Kayte Denslow, Richard Zheng, Mark Bearden

UKY-CAER

Joe Remias (PM) Balraj Ambedkar

DPS

Vinay Mulgundmath (PM) Saravanan Swaminathan, Agnieszka Kuczynska, Scott Hume

NZ

Sonja Salmon (PI/PM) Alan House, Megan Beckner Whitener

Thank You